

**AIP SUPPLEMENT
(SUP)****H70/25****Effective: 202505052000 UTC**

AERONAUTICAL INFORMATION SERVICE,
AIRSERVICES AUSTRALIA, GPO BOX 367,
CANBERRA ACT 2601

For **DISTRIBUTION** queries, contact:
Email: aim.editorial@airservicesaustralia.com

For **CONTENT** queries regarding this SUP, contact:
Email: aaron.pond@bne.com.au

BRISBANE AERODROME (YBBN) LOGISTIC APRON UPGRADE PROJECT

1. INTRODUCTION

- 1.1 This AIP SUP is intended to provide details regarding the construction activities associated with the Logistic Apron Upgrade Project.
- 1.2 Stage 1: 06 May to 09 July 2025
Stage 2: 02 June to 20 June 2025
- 1.3 Details of these works will be provided in *Method of Working Plan (MOWP) YBBN 25/01* which will be distributed to the MOWP distribution list.

2. SCOPE OF WORKS

- 2.1 The scope of work includes rectification of asphalt pavement in the vicinity of Logistic Apron (Bays L1-L4) & adjoining apron taxilane and TWY L, including but not limited to:
 - Removal of existing Aeronautical Ground Lighting (AGL) fittings
 - Profiling of existing asphalt layers
 - Removal of profiled spoil
 - Rejuvenation of 200M of Watermain
 - Redundancy of old Joint User Hydrant Installation infrastructure
 - Application of crack treatment/tack coat
 - Placement of new asphalt base and surfacing layers
 - Painting of line markings
 - Reinstatement of AGL and installation of solar apron edge lights

- Reinstatement of perimeter road, ground support equipment and associated infrastructure
- Re-aiming of apron flood lighting.

Refer to Appendix for location of work details and staging information.

- 2.2 These works are largely weather dependent and should inclement weather (i.e. rain, hail or low visibility conditions) impact the works program such changes will be advised by NOTAM.

3. TECHNICAL QUESTIONS AND ADVICE

- 3.1 Further information or clarification may be obtained by contacting Brisbane Airport Corporation Pty Ltd:

Airfield Compliance Manager

Aaron Pond

Email: Aaron.Pond@bne.com.au

4. CANCELLATION

- 4.1 This SUP will be cancelled when works are completed, expected July 2025.

5. DISTRIBUTION

- 5.1 Airservices Australia website only.

Appendix

1. Works Information

1. Works Information

